

Subdivisional Lines, T 5 N R 32 E W M.

Chains	etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
43.00	Ravine, course W.
80.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 5, 6, 7 & 8. Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; 1st rate.
	E. on random line bet. Secs. 5 & 8.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.73	Intersect N. & S. line at Cor. W. on true line.
40.36	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.73	The Cor. Land; rolling. Soil; 1st rate.
	W. on random line bet. Secs. 6 & 7.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
81.99	Intersect W. Bdy. of Tp., 490 lks. S. of Cor. S.86°30' E. on true line.
7.00	Ravine, course N.W.
41.99	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
81.99	The Cor. Land; rolling. Soil; 1st rate.
	N. on random line bet. Secs. 5 & 6. Var. 21°30' E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
83.50	Intersect N. Bdy. of Tp., 230 lks. E. of Cor. S.1°39' E. on true line.