

Subdivisional Lines, T 5 N R 33 E W M.

Chains

N. bet. Secs. 10 & 11.

Var. 21° E.

40.00 Set $\frac{1}{4}$ Sec. post.

Drove charred stake; dug pits & raised mound, as per instruct.

80.00 Set post Cor. to Secs. 2, 3, 10 & 11 on land gently sloping
to N.E. Drove charred stake; dug pits & raised mound,
as per instructions.

Land; gently rolling.

Grass good.

Soil; 2nd rate.

E. on random bet. Secs. 2 & 11.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

70.00 To small spring creek, 5 lks. wide.

79.50 Intersect N. & S. line, 30 lks. N. of post, from which
I run

N. 89° 47' W. on true line.

39.75 Set $\frac{1}{4}$ Sec. post.

Drove charred stake. Dug pits. Raised mound, as per in-
structions.

79.50 To post Cor.

Land; rolling.

Grass good.

Soil; 2nd rate.

N. on random line bet. Secs. 2 & 3.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

80.00 Intersect E. & W. Twp line at post, from which I run
S. on true line.

40.00 Set $\frac{1}{4}$ Sec. post.

Drove charred stake; dug pits.

80.00 To post Cor.

Land; rolling.

Grass good.

Soil; 2nd rate.