

## Subdivisional Lines, T 5 N R 33 E W M.

Chains	E. on random bet. Secs. 22 & 27.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.80	Intersect N. & S. line, 20 lks. S. of post, from which I run S.89°51' W. on true line.
39.90	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits; raised mound, as per instruct.
79.80	To post Cor. Land; rolling. Grass good. Soil; 2nd rate.
<hr/>	
	N. bet. Secs. 21 & 22.  Var.21°E.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per in- structions.
80.00	Set post Cor. to Secs. 15, 16, 21 & 22. Drove charred stake; dug pits; raised mound, as per in- structions. Land; rolling. Grass good. Soil; 2nd rate.
<hr/>	
	E. on random bet. Secs. 15 & 22.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.70	Intersect N. & S. line, 30 lks. S. of post, from which I run S.89°47' W. on true line.
39.75	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound as per instructions.
79.70	To post Cor. Land; rolling. Grass good. Soil; 2nd rate.