

Subdivisional Lines, T 5 N R 33 E W M.

Chains

E. on random bet. Secs. 3 & 10.

40.00 Set temp. $\frac{1}{2}$ Sec. post.

79.60 Intersect N. & S. line at post, from which I run
W. on true line.

39.80 Set $\frac{1}{2}$ Sec. post. Drove charred stake; dug pits and raised
mound, as per instructions.

79.60 To post Cor.
Land; rolling.
Grass good.
Soil; 2nd rate.

N. on random bet. Secs. 3 & 4.

Var. 21° E.

40.00 Set temp. $\frac{1}{2}$ Sec. post.

79.45 Intersect E. & W. Tp. line, 60 lks. W. of post, from which
I run
S. 14' W. on true line.

39.45 Set $\frac{1}{2}$ Sec. post; drove charred stake and raised mound, as
per instructions, and dug pits.

79.45 To post Cor.
Land; rolling.
Soil; 2nd rate. Grass good.

N. bet. Secs. 32 & 33.

Var. 21° E.

40.00 Set $\frac{1}{2}$ Sec. post; drove charred stake; dug pits & raised
mound, as per instructions.

80.00 Set post Cor. to Secs. 28, 29, 32 & 33; drove charred stake;
dug pits & raised mounds, as per instructions.

Land; rolling.
Grass good.
Soil; 2nd rate.