

Subdivisional Lines, T 5 N R 33 E W M.

Chains	N. bet. Secs. 20 & 21. Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 16, 17, 20 & 21, at hill, facing to the S. Drove charred stake; dug pits & raised mound as per instructions. Land; rolling. Grass good. Soil; 2nd rate.
<hr/>	
	E. on random bet. Secs. 16 & 21.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.60	Intersect N. & S. line, 35 lks. S. of post, from which I run S. 89° 45' W. on true line.
40.30	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
80.60	To post Cor. Land; rolling. Soil; 2nd rate. Grass good.
<hr/>	
	N. bet. Secs. 16 & 17. Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 8, 9, 16 & 17. Drove charred stake; dug pits & raised mound, as per instructions. Grass good. Soil; 2nd rate.
<hr/>	
	May 10th, 1865.
	E. on random line bet. Secs. 9 & 16.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.80	Intersect N. & S. line, 20 lks. N. of post, from which I