

Subdivisional Lines, T 5 N R 33 E W M.

Chains	N.89°51' W. on true line.
39.90	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instruct.
79.80	To post Cor. Land; rolling. Grass good. Soil; 2nd rate.
	N. bet. Secs. 8 & 9. Var.21°E.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
66.00	To road in Canyon, course N.W.
80.00	Set post Cor. for Secs. 4, 5, 8 & 9, on hill, N. side of Canyon, 10 chs. Drove charred stake; dug pits and raised mound, as per instructions. Land; broken. Grass good. Soil; 2nd rate.
	E. on random bet. Secs. 4 & 9.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.10	Intersect N. & S. line at post, from which I run W. on true line.
40.05	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.10	To post Cor. Land; rolling. Grass good. Soil; 2nd rate.
	N. on random bet. Secs. 4 & 5. Var.21°E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.