

Subdivisional Lines, T 5 N R 33 E W M.

Chains	
79.50	Intersect E. & W. Tp. line, 20 lks. W. of post, from which I run S.9' W. on true line.
39.50	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
79.50	To post Cor. Land; rolling. Grass good. Soil; 2nd rate.
N. bet. Secs. 31 & 32.	
Var. 21°E.	
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 30, 29, 31 & 32. Drove charred stake; dug pits & raised mound, as per instructions. Land; rolling. Grass good. Soil; 2nd rate.
E. on random bet. Secs. 29 & 32.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.10	Intersect N. & S. line, 30 lks. N. of post, from which I run N.89°47' W. on true line.
40.05	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
80.10	To post Cor. Land; rolling. Grass good. Soil; 2nd rate.
W. on random bet. Secs. 30 & 31.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.90	Intersect N. & S. Tp. line, 30 lks. N. of post, from which