

Subdivisional Lines, T 5 N R 33 E W M.

Chains

39.70 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

79.70 To post Cor.
Land; rolling.
Grass good.
Soil; 2nd rate.

N. bet. Secs. 19 & 20.
Var. 21° E.

40.00 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

80.00 Set post Cor. for Secs. 17, 18, 19 & 20, on land rolling gently to S. Drove charred stake; dug pits & raised mound, as per instructions.
Land; rolling. Grass good. Soil; 2nd rate.

May 11th, 1865.

E. on random bet. Secs. 17 & 20.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

79.65 Intersect N. & S. line, at post, from which I run
W. on true line.

39.82 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

79.65 To post Cor.
Land; rolling.
Soil; 2nd rate.

W. on random bet. Secs. 18 & 19.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

79.65 Intersect N. & S. Tp. line, 30 lks. S. of post, from which
I run
S. 89° 47' E. on true line.

39.65 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.