

Subdivisional Lines, T 5 N R 33 E W M.

Chains

Land; broken.
Soil; 2nd rate. Grass good.

N. bet. Secs. 7 & 8.

Var.21°E.

40.00 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits and raised mound, as per instructions.

80.00 Set post Cor. for Secs. 5, 6, 7 & 8. Drove charred stake; dug pits and raised mound, as per instructions.

Land; rolling.
Soil; 2nd rate. Grass good.

E. on random bet. Secs. 5 & 8.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

80.10 Intersect N. & S. line, 50 lks. S. of post, from which
I run

S.89°38' W. on true line.

40.05 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits and raised mound, as per instructions.

80.10 To post Cor.

Land; rolling. Grass good. Soil; 2nd rate.

W. on random bet. Secs. 6 & 7.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

80.45 Intersect N. & S. Tp. line, 40 lks. S. of post, from which,
I run

S.89°43'E.

40.45 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits and raised mound, as per instructions.

80.45 To post Cor.

Land; broken.
Soil; 2nd rate. Grass good.