

## Subdivisional Lines, T 5 N R 34 E W M.

Chains	<p>Land; gently sloping to S.W.</p> <p>Good grass.</p> <p>Soil; good 2nd rate.</p>
	<p>E. on random bet. Secs. 24 &amp; 25.</p>
38.00	Trail, course E. of N.
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.
79.84	Intersect N. & S. line, 10 lks. S. of post, from which I run
	S.89°56' W. on true line.
39.92	Set $\frac{1}{4}$ Sec. Cor. post, on level.
	Drove charred stake; dug pits and raised mound, as per instructions.
79.84	To post Cor.
	Land; gently rolling.
	Good grass.
	Soil; good 2nd rate.
	N. bet. Secs. 23 & 24.
	Var. 20° E.
40.00	Set $\frac{1}{4}$ Sec. post Cor. Land slopes gradually to N.E. Drove charred stake; dug pits and raised mound, as per instructions.
80.00	Set post Cor. for Secs. 13, 14, 23 & 24, on S. side of ravine, course E.
	Drove charred stake; dug pits and raised mound, as per instructions.
	Land; gently rolling.
	Good grass.
	Soil; 2nd rate.
	E. on random bet. Secs. 13 & 24.
17.00	Spring branch, 2 lks. wide, course N.E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.