

Subdivisional Lines, T 5 N R 34 E W M.

Chains

N. bet. Secs. 29 & 30.

Var. 20°E.

- 40.00 Set  $\frac{1}{4}$  Sec. post, land slopes to W. Drove charred stake; dug pits & raised mound, as per instructions.
- 80.00 Set post Cor. for Secs. 19, 20, 29 & 30. Land slopes to W. Drove charred stake; dug pits & raised mound, as per instructions.
- Land; broken.
- Soil; good 2nd rate.

E. on random bet. Secs. 20 & 29.

- 40.00 Set temp.  $\frac{1}{4}$  Sec. post.
- 44.00 Trail, course N.W. & S.E.
- 80.09 Intersect N. & S. line, 33 lks. S. of post Cor., from which I run  
S. 89°46' W. on true line.
- 40.04 Set  $\frac{1}{4}$  Sec. post Cor. Land slopes to N.E.  
Drove charred stake; dug pits & raised mound, as per instructions.
- 80.09 To post Cor.  
Land; broken. Good grass. Soil; 2nd rate.

W. on random bet. Secs. 19 & 30.

- 40.00 Set temp.  $\frac{1}{4}$  Sec. Cor.
- 80.21 Intersect N. & S. Tps. line, 25 lks. N. of post Cor. for Secs. 19, 30, 24 & 25, from which I run  
N. 89°49' E. on true line.
- 40.21 Set  $\frac{1}{4}$  Sec. post Cor., on level. Drove charred stake; dug pits & raised mound, as per instructions.
- 80.21 To post Cor.  
Land; gently rolling.  
Grass good.  
Soil; 2nd rate.