

## Subdivisional Lines, T 5 N R 34 E W M.

Chains	
	N. bet. Secs. 19 & 20.
	Var. 20°E.
40.00	Set $\frac{1}{4}$ Sec. post. Land slopes to N.W. Dug pits; drove charred red stake and raised mound, as per instructions.
80.00	Set post Cor. for Secs. 17, 18, 19 & 20. Land slopes to N.W. Drove charred stake; dug pits & raised mound, as per instructions.
	Land; quite broken.
	Soil; 2nd rate.
	Grass good.
	6666
	E. on random bet. Secs. 17 & 20:
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.01	Intersect N. & S: line, 27 lks. S. of post Cor., for Secs. 16, 17, 20 & 21, from which I run S. 89°48' W. on true line.
40.00	Set $\frac{1}{4}$ Sec. post. Land slopes to N. Drove charred stake; dug pits & raised mound, as per instructions.
80.01	To post Cor.
	Land; rolling.
	Good grass.
	Soil; 2nd rate.
	W. on random bet. Secs. 18 & 19:
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.17	Intersect W. Tp. line; 11 lks. N. of post Cor. for Secs. 18, 19, 13 & 24, from which, I run N. 89°55'E. on true line.
40.17	Set $\frac{1}{4}$ Sec. post, on level; drove charred stake; dug pits and raised mound, as per instructions.
80.17	To post Cor.
	Land; rolling.
	Good grass.
	Soil; 2nd rate.