

Exterior Lines,
 N. Bdy., T 5 N R 35 E W M.

Chains

- 38.67 Move temp. $\frac{1}{4}$ Sec. post, 86 lks. N.
 Drove charred stake, dug pits & raised mound, as per instructions.
- 78.67 Set post Cor. for Secs. 5 & 6, 31 & 32.
 Drove charred stake; dug pits & raised mound, as per instructions.
-
- S.89°43'E. on N. Bdy. of Sec. 5.
- 40.00 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits and raised mound, as per instructions.
- 80.00 Set post Cor. for Secs. 4, 5, 32 & 33. Drove charred stake; dug pits & raised mound, as per instructions.
-
- S.89°43'E. on N. Bdy. of Sec.4.
- 40.00 Set $\frac{1}{4}$ Sec. post; dug pits; drove charred stake & raised mound, as per instructions.
- 80.00 Set post Cor. for Secs. 3, 4, 33 & 34. Drove charred stake; dug pits & raised mound, as per instructions.
-
- S.89°43'E. on N. Bdy. Sec. 3.
- 40.00 Set $\frac{1}{4}$ Sec. Cor. post; drove charred stake; dug pits & raised mound, as per instructions.
- 80.00 Set post Cor. for Secs. 2, 3, 34 & 35; drove charred stake; dug pits & raised mound, as per instructions.
-
- S.89° 43'E. on N. Bdy. of Sec. 2. H
- 40.00 Set $\frac{1}{4}$ Sec. post and made stone mound with charred stake, as per instructions.
- 80.00 Set post Cor. for Secs. 1, 2, 35 & 36; from which
 A cottonwood, 10 ins. diam., brs. S.59°30' E., 58 lks. dist.
 A cottonwood, 5 ins. diam., brs. N.76°30'E., 41 lks. dist.