

Exterior Lines,

N. Bdy., T 5 N R 35 E W M.

Chains	<p>A cottonwood, 12 ins. diam., brs. S.2°30'W., 59 lks. dist. Made stone mound; no tree near in Sec.2. April 10th 1865.</p>
	<p style="text-align: right;">H</p> <p>At the S.E. Cor., N. bet. Rs. 35 & 36 on E. Bdy. of Sec. 36, in T. 5 N. Var.20°E.</p>
28.00	A settlers house brs. E. about 20.00.
40.00	Set post Cor. for $\frac{1}{4}$ Sec. Cor. on side hill, facing E.; dug pits; drove charred stake & raised earth mound, as per instructions.
73.00	A wagon road, course N.W.
80.00	Set post Cor. for Secs. 25 & 36, 30 & 31, on hill, facing E.; drove charred stake; dug pits & raised mound, as per instructions.
	<p>This line passes along along hill side, sloping to the E. Good grass. Soil; good 2nd rate.</p>
	<p>N. on E. Bdy. of Sec. 25. Var.20°E.</p>
40.00	Set post Cor. for $\frac{1}{4}$ Sec. Land gently dipping to the E. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 24, 25, 19 & 30. Land slopes to the E. Land descending to the N.E. Good grass. Soil; good 2nd rate.
	<p>N. on E. Bdy. of Secs. 24. Var.21°E.</p>
40.00	Set post Cor. for $\frac{1}{4}$ Sec. on hillside facing E. Drove charred stake; dug pits & raised mound, as per instructions.