

Subdivisional Lines, T 5 N R 35 E W M.

Chains	
80.12	Intersect Tp. line, 8 lks. S. of post. Thence S.89°53'W. on true line bet. Secs. 25 & 36.
23.62	Road, course N. of W.
40.06	Set post Cor. for $\frac{1}{4}$ Sec. Drove charred stake; dug pits; raised mound, as per instructions.
80.12	To post Cor. Land; gently rolling. Good grass. Soil; good rate.
N. bet. Secs. 25 & 26. Var.21°E.	
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits; raised mound, as per instructions.
80.00	Set post Cor. for Secs. 23, 24, 25 & 26. Drove charred stake; dug pits; raised mound, as per instructions. The land in this Sec. is gently rolling, covered with good grass. Soil; 2nd rate.
E. on random line bet. Secs, 24 & 25. Var.21°E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.19	Intersect N. & S. line, 20 lks. S. of post. Correction will be S.89°39'W. on true line.
11.00	Road, course W. of N.
40.09 $\frac{1}{2}$	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits; raised mound, as per instructions.
56.00	Road, course W. of N.
80.19	To post Cor. Land gently rolling. Good grass. Soil; good 2nd rate.