

Subdivisional, Lines, T 5 N R 35 E W M.

Chains	
79.25	<p>The Cor. to Secs. 1, 2, 11 & 12.</p> <p>Land; level.</p> <p>Timber; balm & alder.</p> <p>Soil; 2nd rate.</p>
	<p>N. bet. Secs. 1 & 2, on random.</p> <p style="text-align: right;">Var. 21° E.</p>
40.00	Set temp. $\frac{1}{4}$ Sec. Cor. post.
52.00	Bank of creek, bottom, course N.W.
80.55	<p>Intersect E. & W. line, 10 lks. E. of post; from which I</p> <p style="text-align: center;">run</p> <p>S. 4° E. on true line.</p>
40.27	Set $\frac{1}{4}$ Sec. post; dug pits; raised mound; drove charred stake, as per instructions.
80.55	<p>To post Cor.</p> <p>Land; level.</p> <p>Timber; balm.</p> <p>Soil; gravelly.</p>
	<p>April 10th, 1865.</p> <p>N. bet. Secs. 34 & 35.</p>
40.00	Set post for $\frac{1}{4}$ Sec. Cor. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	<p>Set post Cor. for Secs. 26, 27, 34 & 35. Drove charred stake; dug pits; raised mound, as per instructions.</p> <p>Land; rolling gently.</p> <p>Grass good.</p> <p>Soil; 2nd rate.</p>
	E. on random bet. Secs. 26 & 35.
30.00	Dry creek, 25 lks. wide, course N.W.
35.00	Road, course, N.W. & S.E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.85	Intersect N. & S. line, 50 lks. S. of post; from which Cor.