

Subdivisional Lines, T 5 N R 36 E W M.

Shains	N. on random bet. Secs. 2 & 3.
	Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.50	Intersect E. & W. Tp. line, 30 lks. W. of post; from which I run S. 13' W. on true line.
39.50	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
79.50	To post Cor. Land; rolling. Grass; good. Soil; 2nd rate.
	N. bet. Secs. 33 & 34.
	Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post near ravine, hillside facing W. Drove charred stake; dug pits & raised mound, as per instruc- tions.
80.00	Set post Cor. for Secs. 27, 28, 33 & 34. Drove charred stake; dug pits & raised mound, as per instructions. Land; rolling. Grass; good. Soil; 2nd rate.
	E. on random bet. Secs. 27 & 34.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.20	Intersect N. & S. line, 50 lks. N. of post; from which, I run N. 89° 38' W. on true line.
40.10	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits; raised mound, as per instructions.
80.20	To post Cor. Land; rolling. Grass; good. This line passes near some springs. Soil; 2nd rate.