

Subdivisional Lines, T 5 N R 36 E W M.

Chains	May 17th, 1865.
	E. on random bet. Secs. 10 & 15.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.18	Intersect N. & S. line, 10 lks. N. of post; from which, I run
	N.89° 56' W. on true line.
39.84	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
70.50	Road, course N.
79.18	Post Cor.
	Land; rolling.
	Grass; good.
	Soil; 2nd rate.
	N. bet. Secs. 9 & 10.
	Var.21° E.
40.00	Set $\frac{1}{4}$ Sec. post. Land descending to E. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 3, 4, 9 & 10. Drove charred stake; dug pits and raised mound, as per instructions.
	Land; rolling.
	Grass; good.
	Soil; 2nd rate.
	E. on random bet. Secs. 3 & 10.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.88	Intersect N. & S. line, 28 lks. S. of post; from which, I run
	S.89°48' W. on true line.
34.50	To road, course N.W.
39.94	Set $\frac{1}{4}$ Sec. post, on E. side of dry ravine. Settler's house S. about 40 chs.
79.88	To post Cor.
	Land; rolling.
	Soil; 2nd rate.
	Grass; good.