

Subdivisional Lines, T 5 N R 36 E W M.

Chains	
40.00	Set $\frac{1}{4}$ Sec. post on hillside, sloping N.E. Drove charred stake; dug pits and raised mound, as per instructions.
80.00	Set post Cor. for Secs. 20, 21, 28 & 29. Drove charred stake; dug pits & raised mound, as per instructions. Land; rolling. Grass; good. Soil; 2nd rate.
	E. on random bet. Secs. 21 & 28.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.69	Intersect N. & S. line, 32 lks. S. of post; from which, I run S.89°46' W. on true line.
39.84	Set $\frac{1}{4}$ Sec. post on hill, sloping to N. Drove charred stake; dug pits & raised mound, as per instructions.
79.69	To post Cor. Land; broken. Grass; good. Soil; 2nd rate.
	N. bet. Secs. 20 & 21. H
	Var.21° E. .
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits and raised mound, as per instructions.
42.00	To edge of bluff.
58.70	To Walla Walla River, 169 lks. wide, course N.W.
80.00	Set post Cor. for Secs. 16, 17, 20 & 21. Drove charred stake; dug pits & raised mound, as per instructions. Land; in creek bottom, timbered with balm, birch & alder. Soil; 1st rate.
	E. on random bet. Secs. 16 & 21.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.76	Intersect N.&.S. line, 42 lks. S. of post; from which, I run S.89°42' W. on true line.