

Subdivisional Lines, T 5 N R 36 E W M.

Chains	<p>stake; dug pits & raised mound, as per instructions.</p> <p>Land; rolling.</p> <p>Grass; good.</p> <p>Soil; 2nd rate.</p>
	<p>E. on random bet. Secs. 20 & 29.</p>
40.00	Set temp. post.
79.88	Intersect N. & S. line at post; from which I run
	W. on true line.
39.94	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
79.88	To post Cor.
	Land; rolling.
	Grass; good.
	Soil; 2nd rate.
	<p>W. on random bet. Secs. 29 & 30.</p>
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.00	Intersect N. & S. Tps. line, 18 lks. S. of post; from which, I run
	S. 89° 52' E. on true line.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	To post Cor.
	Land; rolling.
	Grass; good.
	Soil; 2nd rate.
	<p>N. bet. Secs. 19 & 20. H</p> <p style="text-align: center;">Var. 21° E.</p>
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
46.00	To brink of steep hill. Hill too steep to descend, thence I run W. 5.50; from which point, a small tree on N. & S. line, brs. N. 29° E., making a distance from offset to