

E. Bdy., T 5 N R 37 E W M.

Chains	
40.00	Set stone, 12 x 9 x 7, in mound of earth, with pits; from which A fir, 10 ins. diam., brs. S.20°W., 3 lks. dist.
80.00	Set post for Cor. to Secs. 7, 12, 13 & 18. A red fir, 8 ins. diam., brs. N.55°E., 23 lks. dist. A " " 7 " " " S.50°E., 41 " " A " " 4 " " " S.70°W., 10 " " A white" 6 " " " N.28°W., 28 " "
	Land; hilly. Timber; fir, pine & spruce.
	N. bet. Secs. 7 & 12. Var.20°E.
25.50	Road, E. & W.
40.00	Set post for $\frac{1}{2}$ Sec. Cor.; from which A spruce, 20 ins. diam., brs. S.44°W., 71 lks. dist. A fir, 10 ins. diam., brs. N.20°E., 30 lks. dist.
46.95	Road, E. & W.
51.40	Enter wet prairie swamp.
54.48	Creek, 8 lks. wide, falls S.W.
55.30	Road, S.W. & N.E.
56.20	Enter timber.
74.50	Enter prairie.
80.00	Set post, in edge of prairie, Cor. for Secs. 1, 6, 7, & 12; from which A white fir, 8 ins. diam., brs. S.78°W., 52 lks. dist. A white fir, 6 ins. diam., brs. N.35°W., 40 lks. dist. No other trees convenient. Timber; pine, fir, spruce & tamarack. Land; rolling to prairie, which is wet, requires draining for agriculture. Soil; 1st rate, black loam.
	N. bet. Secs. 1 & 6, on random line. Var.18°E.