

Subdivisional Lines, T 5 N R 37 E W M.

Chains	Land; rolling. Timber; pine & fir.
	E. on random line bet. Secs. 26 & 35.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.70	Intersect N. & S. line, 38 lks. N. of Cor. for Secs. 25, 26, 35 & 36; from which Cor., I run N.89°44' W. on true line bet. Secs. 26 & 35.
29.70	Bottom of ravine, falls N.W.
39.85	Set post for $\frac{1}{4}$ Sec. Cor.; from which A fir, 10 ins. diam., brs. N.15°W., 71 lks. dist. A " 13 " " " S.42°E., 26 " "
79.70	The Cor. for Secs. 26, 27, 34 & 35.
	N. bet. Secs. 26 & 27. Var. 21°E.
40.00	Set post on steep hillside facing W., for $\frac{1}{4}$ Sec. Cor. A fir, 9 ins. diam., brs. N.21°E., 47 lks. dist. A fir, 18 ins. diam., brs. N.37°W., 81 lks. dist.
80.00	Set stone, 21 x 23 x 30, mound of stone for Cor. to Secs. 22, 23, 26 & 27; from which A pine, 18 ins. diam., brs. S.22°E., 85 lks. dist. A fir, 10 ins. diam., brs. S.14°W., 141 lks. dist.
	Land; mountainous. Timber; pine & fir.
	E. on random line bet. Secs. 23 & 26.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.38	Intersect N. & S. line, 51 lks. S. of Cor. for Secs. 23, 24, 25 & 26; from which Cor., I run S.89°38' W. on true line bet. Secs. 23 & 26.
12.38	Spur falls S., 150 ft. Descend.
24.00	Bottom of ravine.
40.19	Set post for $\frac{1}{4}$ Sec. Cor.; from which A fir, 12 ins. diam., brs. N.32°E., 29 lks. dist. A fir, 7 ins. diam., brs. N.65°W., 58 lks. dist.