

Subdivisional Lines, T 5 N R 37 E W M.

Chains	
14.40	Ridge, N.W.
39.70	Set post for $\frac{1}{4}$ Sec. Cor.; from which A tamarack, 8 ins. diam., brs. N.20°W., 83 lks. dist. A fir, 14 ins. diam., brs. S.15°E., 24 lks. dist.
58.40	Leave timber.
79.40	The Cor. for Secs. 2, 3, 10 & 11. Land; rolling. Timber; pine & fir.
<hr/>	
	N. bet. Secs. 2 & 3, on random line. Var. 20°30'E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.36	Intersect N. Bdy. of Tp., 113 lks. W. of stone Cor. for Secs. 2, 3, 34 & 35; from which Cor., I run S.47' W. on true line bet. Secs. 2 & 3.
15.36	Ridge falls W.
27.00	Creek, 8 lks. wide, falls W.
40.36	Set stake for $\frac{1}{4}$ Sec. Cor.
44.36	Enter timber; descend.
60.00	Leave timber.
80.36	The Cor. for Secs. 2, 3, 10 & 11. Land; mountainous. Timber; pine & fir.
	Nov. 2nd, 1872.
<hr/>	
	N. bet. Secs. 33 & 34. Var. 20 $\frac{3}{4}$ °E.
17.00	Ravine, branch, 6 lks. wide, flows N.W.
40.00	Set post for $\frac{1}{4}$ Sec. Cor. on side hill face S.E.
73.00	Summit of ridge.
80.00	Set post & marked stone for Cor. to Secs. 27, 28, 33 & 34, on steep side hill face N.W. Land; mountainous. Timber; pine & fir.
<hr/>	