

Subdivisional Lines, T 5 N R 37 E W M.

Chains	E. on random line bet. Secs. 27 & 34.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.73	Intersect N. & S. line, 41 lks. N. of Cor. for Secs. 26, 27, 34 & 35; from this Cor., I run N.89°43' W. on true line bet. Secs. 27 & 34.
31.73	Leave timber.
39.86	Set post, charred stake, for $\frac{1}{4}$ Sec. Cor.
79.73	The Cor. for Secs. 27, 28, 33 & 34. Land; mountainous. Timber; tamarack & pine.
N. bet. Secs. 27 & 28. Var. 21° E.	
40.00	Set stone, 10 x 10 x 12, for $\frac{1}{4}$ Sec. Cor.
63.00	Enter timber.
63.78	Tall pine, 18 ins. diam.
64.00	Bottom of mountain, 900 ft.
64.73	N. Fork Walla Walla river, 35 lks. wide, W.
67.27	Timber road.
68.00	Leave bottom; ascend steep Russell bluff; leave timber.
80.00	Set stone, 4 x 8 x 20 for Cor. to Secs. 21, 22, 27 & 28. Land; mountainous. Timber; pine, fir & birch.
E. on random line bet. Secs. 22 & 27.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.20	Intersect N. & S. line, 55 lks. S. of Cor. for Secs. 22, 23, 26 & 27; from this Cor., I run S.89°36' W. on true line bet. Secs. 22 & 27.
31.20	Basalt cliff, 100 ft. offset 10 chs. to pass.
33.00	Enter bottom.
35.00	N. Fork of Walla Walla, 68 lks. wide, S.W.
39.00	Road to timber.
40.10	Set post for $\frac{1}{4}$ Sec. Cor. & rock, 10 x 12 x 13. A pine, 20 ins. diam., brs. N.44° E., 55 lks. dist.
42.00	Leave timber; descend.