

Subdivisional Lines, T 5 N R 37 E W M.

Chains 80.20	The Cor. of Secs. 21, 22, 27 & 28. Land; mountainous. Timber; tamarack & alder. Nov. 4th, 1872.
	N. bet. Secs. 21 & 22. Var. 23° E.
40.00	Set stone, 11 x 14 x 16 for $\frac{1}{4}$ Sec. Cor.
80.00	Set stone, 3 x 20 x 32 for Cor. to Secs. 15 & 16, 21 & 22, on side hill face S.E. Land; rocky. No timber. Good grass.
	E. on random line bet. Secs. 15 & 22.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.65	Intersect N. & S. line, 41 lks. N. of Cor. for Secs. 14, 15, 22 & 23; from this Cor., I run N. 89° 43' W. on true line bet. Secs. 15 & 22.
31.61	Ravine falls S.W, 100 ft.
39.82	Set stone, 18 x 22 x 20 for $\frac{1}{4}$ Sec. Cor.
79.65	The Cor. for Secs. 15, 16, 21 & 22. No timber. Good grass.
	N. bet. Secs. 15 & 16. Var. 21° E.
16.00	Summit of ridge, E. & W., 500 ft. descend.
29.00	Bottom of ravine.
40.00	Set stone, 12 x 14 x 18 for $\frac{1}{4}$ Sec. Cor.
45.00	Road to valley.
55.00	Enter timber.
65.00	Leave timber.
80.00	Set stone, 14 x 17 x 24, for Cor. to Secs. 9, 10, 15 & 16. Land; mountainous. Timber; tamarack & pine.