

Subdivisional Lines, T 5 N R 37 E W M.

Chains.	E. on random line bet. Secs. 10 & 15.
40.00	Set stone for temp. $\frac{1}{4}$ Sec. Cor.
80.35	Intersect N. & S. line, 37 lks. N. of Cor. for Secs. 10, 11, 14 & 15; from this Cor., I run S.89°44' W. on true line bet. Secs. 10 & 15.
4.35	Leave scattering timber.
35.50	Creek, 8 lks. wide, N.W.
40.18	Set stone for $\frac{1}{4}$ Sec. Cor., mound & pits.
68.17	Bottom of ravine; ascend.
80.35	The Cor. for Secs. 9, 10, 15 & 16. Land; mountainous. Timber; pine & fir.
	N. bet. Secs. 9 & 10. Var. 22 $\frac{1}{2}$ ° E.
28.40	Creek, 2 lks. wide, falls N.E
38.00	Road to timber.
40.00	Set stone for $\frac{1}{4}$ Sec. Cor., 8 x 12 x 15.
45.30	Road to timber.
80.00	Set stone, 10 x 12 x 14, for Cor. to Secs. 3, 4, 9 & 10. Timber on ravine. Good grass. Nov. 5th, 1872.
	E. on random line bet. Secs. 3 & 10.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.46	Intersect N. & S. line, 52 lks. N. of Cor. for Secs. 2, 3, 10 & 11; from which Cor., I run N.89°38' W. on true line bet. Secs. 3 & 10.
39.76	Set stone, 7 x 8 x 10, for $\frac{1}{4}$ Sec. Cor.; descend.
79.46	The Cor. for Secs. 3, 4, 9 & 10. Soil; good. No timber. Good grass.