

Exterior Lines, T 5 N R 39 E W M.

Chains	
28.25	A spruce, 36 ins. diam., 100ft. below top of ridge.
39.15	Spring branch, 3 lks. wide, runs E., 300 ft. below line tree.
40.00	Set basalt stone, 15 x 13 x 10 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., 30 ft. above branch, marked $\frac{1}{4}$ on W. face, raised mound of stone alongside. Pits impracticable.
55.75	Top of ridge brs. E. & W., 400 ft. above $\frac{1}{4}$ Sec. Cor.
66.40	Ravine, course E., 150 ft. below top of ridge.
78.50	Enter prairie, brs. N.E. & S.W., 100 ft. above ravine.
80.00	Set basalt stone, 18 x 12 x 8 ins., 12 ins. in ground, for Cor. to Secs. 7, 18, 12 & 13, 30 ft. above point of entering prairie, marked with 4 notches on S. and 2 notches on N. edges; from which A spruce, 24 ins. diam., brs. N.72°E., 109 lks. dist., marked T 5 N R 39 E S 7 B T. A fir, 9 ins. diam., brs. N.79°W., 102 lks. dist., marked T 5 N R 38 E S 12 B T. A fir, 12 ins. diam., brs. S.59°W., 123 lks. dist., marked T 5 N R 38 E S 13 B T. A spruce, 20 ins. diam., brs. S.63°E., 98 lks. dist., marked T 5 N R 39 E S 18 B T. Land; mountainous. Soil; 3rd & 4th rate. Timber; spruce, fir & pine and Some undergrowth of spruce, fir & pine.
<hr/>	
	N. bet. Secs. 7 & 12. Var. 23°E.
1.50	Leave prairie brs. N.E. & S.W.
7.00	Enter prairie brs. N.W. & S.E.
10.00	Top of Divide bet. N. & S. forks of Walla Walla river, brs. N.E. & S.W., 200 ft. above Sec. Cor.
12.50	Leave prairie brs. E. & W., 30 ft. below top of Divide.
14.88	A spruce, 36 ins. diam., 100 ft. below point of leaving prairie.
32.50	Blazed trail brs. N.E. & S.W., 50 ft. below line tree.