

Dependent Resurvey E. Bdy., T 5 N R 38 E W M.

Chain	
	N.0°22'W., on true line on E. Bdy. of Sec. 24.
	Asc. 486 ft. over S. slope, through scattering timber and scattering undergrowth.
12.10	Spur, slope SW.; desc. 76 ft. over NW. slope.
21.70	Small ravine, course W.; asc. 102 ft. over SW. slope.
32.00	Small spur, slopes W.; desc. 34 ft. over NW. slope.
38.25	Small ravine, course N.70°W.; asc. 10 ft. over SW. slope.
38.59	Proportionate point for the $\frac{1}{4}$ Sec. Cor. of Sec.24 only.
	Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for $\frac{1}{4}$ Sec. Cor. of Sec.24 only, with brass cap marked
	$\frac{1}{4}$ S24 1935
	from which
	A fir, 36 ins. diam., brs. S.59 $\frac{1}{2}$ °W., 75 lks. dist., marked $\frac{1}{4}$ S 24 B T.
	A fir, 38 ins. diam., brs. N.82°W., 69 lks. dist., marked $\frac{1}{4}$ S 24 B T.
	Continue to asc. 20 ft. over SW. slope.
40.35	Spur, slopes W.; desc. 21 ft. over NW. slope.
42.10	Ravine, course S.70°W.; asc. 646 ft. over SW. slope.
58.80	Ridge spur, slopes S.50°E.; desc. 77 ft. over NE. slope.
60.10	Dim trail, brs. NW. & SE.
71.10	Ravine, course E.; asc. 52 ft. over SE. slope.
74.10	Spur, slopes E.; desc. 102 ft. over NE. slope.
77.18	The original Cor. established for Secs. 13, 18, 19 & 24, which is basalt stone, 24 x 16 x 12 ins., firmly set, marked with 3 notches on N. and 3 notches on S. edges.
	I now change this Cor. to refer to Secs. 13 & 24 only.
	At point for Cor.
	Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, for Cor. to Secs. 13 & 24 only, with brass cap, marked
	T5N T5N S13 R39E S24 S19 R38E 1935
	from which
	No trace of old NE. bearing tree.
	A fir snag, 40 ins. diam., brs. S.20°E., 36 lks. dist.,