

Dependent Resurvey E. Bdy., T 5 N R 38 E W M.

Chains.

marked T 5 N R 39 E S 19 B T. (Old B.T.)

A fir, 30 ins. diam., brs. S. 7° W., 81 lks. dist.,  
(Not S. 37° W., 70 lks. dist.) with old marks grown  
over. ( Old B.T.)

A fir, 30 ins. diam., brs. N. 85° W., 42 lks. dist.,  
(Not 46 lks. dist.) marked T 5 N R 38 E S 13 B T.  
(Old BT.)

Obliterate the marks on old bearing tree referring  
to T 5 N R 39 E.

Land; mountainous.  
Soil; rocky loam, sandy, 3rd rate.  
Timber; pine, fir, spruce and tamarack.  
Undergrowth; alder, vinemaple, laurel, huckleberry, salal,  
willow, mountain ash, fern and Oregon grape.

N. 0° 20' E., on true line on E. Bdy. of Sec. 13.

Desc. 38 ft. over NE. slope, through scattering timber &  
scattering undergrowth.

- 1.35 Ravine, course E.; asc. 55 ft. over SE. slope.
- 4.15 Spur, slopes E.; desc. 53 ft. over NE. slope.
- 8.15 Ravine, course SE.; asc. 246 ft. over S. slope.
- 14.00 Spur, slopes SE.; continue to asc. 246 ft. over SE. slope.
- 27.70 Spur, slopes E.; desc. 257 ft. over NE. slope.
- 40.03 Proportionate point for 1/4 Sec. Cor. of Sec. 13 only.

Set an iron post, 3 ft. long, 1 in. diam., 8 ins. in the  
ground to solid rock and in mound of stone to top, for  
1/4 Sec. Cor. of Sec. 13 only, with brass cap, marked

1/4 S 13  
1935

from which

A fir, 8 ins. diam., brs. S. 11° W., 432 lks. dist.,  
marked 1/4 S 13 B T.

A fir, 10 ins. diam., brs. N. 56° W., 356 lks. dist.,  
marked 1/4 S 13 B T.

Continue to desc. 30 ft. over NE. slope.

- 41.55 Creek, 1 lk. wide, course E.; asc. 81 ft. over SE. slope.
- 45.50 Spur, slopes S. 70° E.; desc. 60 ft. over NE. slope.
- 48.15 Spring, on line, drains E.
- 55.75 Ravine, course SE.; asc. 173 ft. over SE. slope.
- 57.55 Spur, slopes SE.; desc. 106 ft. over NE. slope.
- 68.95 Ravine, course E.; asc. 121 ft. over SE. slope.
- 80.06 The original Cor. established for Secs. 7, 12, 13 & 18,  
which is basalt stone, 15 x 10 x 8 ins., buried 8 ins.