

Subdivisional Lines, T 5 N R 38 E W M.

Chains	
24.50	Branch of S. Fork of Walla Walla River, 20 lks. wide, flows S.70°E.; thence ascend steep, stony hill; brs. N.W. and S.E.
37.00	Top of rocky spur; brs. N.55°E. and S.55°W.; thence gradually ascending along hillside, through heavy timber.
40.01	A point, 400 ft. above Sec. Cor. and Set an ironstone, 24 x 20 x 10 ins., 18 ins. in mound of stone on rock bed, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face; from which A fir, 30 ins. diam., brs. S.35°W., 20 lks. dist., marked $\frac{1}{4}$ S 25 B T. A fir, 10 ins. diam., brs. N.15°W., 26 lks. dist., marked $\frac{1}{4}$ S 24 B T.
46.00	Ravine, course N.60°E.; ascend mountain top; brs. N.20°E. and S.20°W.
55.00	Leave heavy timber; brs. N. & S.; thence through scattering timber.
59.00	Summit; descend steep slope; brs. N.50°W. and S.50°E.
61.00	Trail; brs. with ridge.
70.00	Leave heavy timber.
75.60	Bottom of ravine, course S.; ascend; hill brs. N.E & S.W.
78.60	Leave timber, brs. N. & S.
80.02	The Cor. of Secs. 23, 24, 25 & 26. Land; mountainous. Soil; gravelly and stony, 3rd & 4th rates. Heavily timbered with pine, fir, tamarack and spruce, 26 chs. Undergrowth; pine, fir, chaparral, tamarack, alder, willow, spruce, yew, huckleberry and bunch grass. Mountainous, or heavily timbered land, 80.02 chs. July 24, 1899.
1.50	N.0°1' W., bet. Secs. 23 & 24. Ascending bare ridge; N.50°E. and S.50°W.
3.00	Enter heavy timber; brs. N.50°E. and S.50°W.
6.00	Bottom of ravine, 200 ft. deep, course W.; ascend; hill brs.