

Subdivisional Lines, T 5 N R 38 E W M.

<p>Chains</p> <p>80.00</p>	<p>A point, 400 ft. above $\frac{1}{4}$ Sec. Cor. and</p> <p>A spruce, 30 ins. diam., for Cor. of Secs. 11, 12, 13 & 14,</p> <p>I mark</p> <p style="padding-left: 40px;">T 5 N S 12 on N.E.</p> <p style="padding-left: 40px;">R 38 E S 13 on S.E.</p> <p style="padding-left: 40px;">S 14 on S.W. and</p> <p style="padding-left: 40px;">S 11 on N.W. sides, with</p> <p style="padding-left: 40px;">4 notches on S. and</p> <p style="padding-left: 40px;">1 notch on E. sides;</p> <p>from which</p> <p style="padding-left: 40px;">A fir, 10 ins. diam., brs. N.70°E., 43 lks. dist.,</p> <p style="padding-left: 40px;">marked T 5 N R 38 E S 12 B T.</p> <p style="padding-left: 40px;">A tamarack, 28 ins. diam., brs. S.11$\frac{1}{2}$°E., 42 lks. dist.,</p> <p style="padding-left: 40px;">marked T 5 N R 38 E S 13 B T.</p> <p style="padding-left: 40px;">A fir, 12 ins. diam., brs. S.28°W., 28 lks. dist.,</p> <p style="padding-left: 40px;">marked T 5 N R 38 E S 14 B T.</p> <p style="padding-left: 40px;">A tamarack, 30 ins. diam., brs. N.58°W., 42 lks. dist.,</p> <p style="padding-left: 40px;">marked T 5 N R 38 E S 11 B T.</p> <p>Land; mountainous.</p> <p>Soil; gravelly & stony, 3rd & 4th rates.</p> <p>Timber; fir, tamarack, spruce and pine.</p> <p>Undergrowth; fir, chaparral, tamarack, yew, spruce, pine,</p> <p style="padding-left: 40px;">alder, willow and bunch grass.</p> <p>Mountainous land: 80.00 chs.</p>
<p>40.00</p> <p>80.24</p>	<p>E. on random line bet. Secs. 12 & 13.</p> <p>Set temp. $\frac{1}{4}$ Sec. Cor.</p> <p>A point, 200 ft. above Sec. Cor. W. and</p> <p>Intersect E. Bdy. of Tp., 48 lks. S. of Cor. of Secs. 7, 12,</p> <p style="padding-left: 40px;">13 & 18, reestablished by me, July 21, 1899, a basalt</p> <p style="padding-left: 40px;">stone, 10 x 8 x 5 ins., above ground, marked & witnessed</p> <p style="padding-left: 40px;">as described in notes of resurvey returned to the Survey-</p> <p style="padding-left: 40px;">or General.</p> <p>Thence I run</p> <p>S.89°40'W. on true line bet. Secs. 12 & 13.</p>