

## Subdivisional Lines, T 5 N R 38 E W M.

Chains	Thence I run S.89°50'W., on true line bet. Secs. 14 & 23. Descending through heavy timber; hill brs. N. & S.
4.50	Branch, 10 lks. wide, runs S.10°E.; ascend E. slope.
29.00	Scattered trail, brs. N.30°E. and S.30°W., scant timber.
38.25	Summit of divide bet. Forks of Walla Walla River; A high, rocky spur, 750 ft. above Sec. Cor., brs. N.20°E. and S.20°W. Descend westward slope.
40.00	A point, 100 ft. below divide and Set basalt stone, 24 x 12 x 8 ins., 18 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, and raise mound of stone, 2 ft. base, 1 $\frac{1}{2}$ ft. high, N. of Cor. Pits impract.
41.50	Enter timber, brs. N. & S.
45.00	Hill brs. N.30°W. and S.30°E.
46.00	Leave timber, brs. N.30°E. and S.30°W. Thence through dense undergrowth.
53.92	Branch, 8 lks. wide, runs N.W.; enter timber, brs. NW. & SE.
65.50	Ravine, course N.30°W.
74.50	Foot of hill; ascend N.E. slope.
79.50	Ridge point brs. S.50°E.
80.00	The Cor. of Secs. 14, 15, 22 & 23. Land; mountainous. Soil; stony, 4th rate. Timber; fir, tamarack, pine & spruce. Undergrowth; chaparral, fir, tamarack, spruce, alder, willow and bunch grass. Mountainous land; 80.00 chs.
	July 27: N.0°2' W., bet. Secs. 14 & 15. Descending steep hill through heavy timber brs. E. & W.
5.00	Hill brs. N.60°W. and S.60°E.
11.75	Bottom of ravine. Ascend.
13.70	A pine, 24 ins. diam., on line, I mark with 2 notches on N. &