

Subdivisional Lines, T 5 N R 38 E W M.

Chains

32 and 33.

August 3; 1899.

August 4:

S.89°52'W. on true line bet. Secs. 29 & 32.

Descending through heavy timber and undergrowth.

Hill brs. N. & S.

1.98 Branch, 10 lks. wide, runs N.W.

Ascend.

6.25 Top of ridge-point, brs. N.W.

Descend.

10.15 Bottom of ravine, 10 ft. deep, course N.50°W.

Ascend.

15.50 Top of narrow ridge, brs. N.

Descend.

23.02 Foot.

Stream, 4 lks. wide, runs N.

Ascend steep hill through scattering timber, brs. N. & S.

38.50 Top of rise.

Descend gradually through heavy timber.

40.18 A point, 1000 ft. above Sec. Cor. and

Set fir post, $3\frac{1}{2}$ ft. long, 3 ins. sq., 24 ins. in ground,

for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on N. face; from which

A tamarack, 14 ins. diam., brs. N.50°E., 19 lks. dist.,
marked $\frac{1}{4}$ S 29 B.T.

A tamarack, 16 ins. diam., brs. S.66°W., 27 lks. dist.,
marked $\frac{1}{4}$ S 32 B.T.

51.25 Foot.

Dry bed of stream, 8 lks. wide, course N.10°W.

Ascend N.E. slope.

54.75 Top of rise on point, course N.

Descend.

57.50 Foot; dry bed of stream, 4 lks. wide, course N.E.

Ascend.

62.50 Leave heavy timber and enter upon old burns.

77.50 Top of ridge-point, brs. N.20°E.

Leave burn and descend through heavy timber and undergrowth