

Subdivisional Lines, T 5 N R 38 E W M.

Chains	
5.00	Top of ridge-point, brs. S. Descend S.W. slope.
10.50	Bottom of ravine, course S.5°E. Ascend steep hill through dense undergrowth, brs. N. & S.
37.96	A spruce, 28 ins. diam., on line, I mark with 2 notches on E. and W. sides; scattered undergrowth.
38.00	Summit of ridge, brs. N. & S. Descend, gradually through heavy timber. Hill brs. N. & S.
40.10	A point, 950 ft. above Sec. Cor. and Set white fir post, 3½ ft. long, 4 ins. sq., 24 ins. in ground, for ¼ Sec. Cor., marked ¼ S on N. face; from which A fir, 22 ins. diam., brs. N. 31½°E., 44½ lks. dist., marked ¼ S 17 B T. A spruce, 22 ins. diam., brs. S. 7¼°E., 25 lks. dist., marked ¼ S 20 B T.
44.05	A fir, 30 ins. diam., on line, I mark with 2 notches on E. and W. sides.
45.95	Foot. Stream, 5 lks. wide, runs S.50°W. Ascend gradually.
47.35	Settler's trail to grazing grounds S., brs. N. and S.
53.80	Wood road, brs. N.15°W. & S.15°E.
61.00	Top of rise & descend gradually. Hill brs. N.60°W. & S.60°E.
67.75	Wood road, brs. N.20°W. & S.20°E.
69.50	Foot of descent. Stream, 3 lks. wide, runs S. 20°E. Ascend gradually. Hill brs. N. & S.
70.75	Settler's trail, brs. N. & S.
73.02	A fir, 30 ins. diam., on line, I mark with 2 notches on E. & W. sides. Descend.