

7.

Subdivisional Lines, T 5 N R 39 E W M.

Chains	
	W. on true line bet. Secs. 30 & 31.
	Desc. 251 ft. over SW. slope, changing to W. slope through heavy second growth timber and dense undergrowth.
6.00	Ravine, course NW.; asc. 61 ft. over NE. slope.
10.00	Small spur, slopes N.; desc. 612 ft. over NW. slope.
30.50	S. Fork of Walla Walla River Trail, brs. NE. and SW.
30.90	Stone monument, marked U.S.G.S. P.T.B.M. elev. 3342, brs. N., 1.10 chs. dist.
31.05	S. Fork of Walla Walla River, 30 lks. wide, course S.20°W.; Ascend 381 ft. over E. slope.
40.00	Set an iron post, 3 ft. long, 1 in. diam., 15 ins. in the ground, for $\frac{1}{4}$ Sec. Cor., with brass cap, marked
	$\begin{array}{c} \frac{1}{4} \text{ S } 30 \\ \hline \text{S } 31 \\ 1932 \end{array}$
	from which
	A fir, 14 ins. diam., brs. N.22°W., 42 lks. dist., marked $\frac{1}{4}$ S 30 B T.
	A fir, 10 ins. diam., brs. S.13°E., 54 lks. dist., marked $\frac{1}{4}$ S 31 B T.
	Continue to asc. 432 ft. over E. slope.
50.00	Small spur, slopes NE.; continue to asc. 250 ft. over NE. slope.
69.40	Ravine, course NE.; continue to asc. 557 ft. over E. slope, changing to NE. slope.
80.00	Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for Cor. to Lots 1, 2, 7 & 8, with brass cap, marked
	$\begin{array}{c} \text{S } 30 \\ 7 \text{ } 8 \\ \hline 2 \text{ } 1 \\ \text{S } 31 \\ 1932 \end{array}$
	from which
	A fir, 10 ins. diam., brs. N.21°E., 65 lks. dist., marked L 8 S 30 B T.
	A fir, 36 ins. diam., brs. S.7°W., 50 lks. dist., marked L 2 S 31 B T.