

Subdivision of T 5 N., R. 39 E.

| Chains | | Feet |
|--------|---|------|
| | $\begin{array}{r} S\ 6 \\ \frac{1}{4} S\ 7 \\ \hline 1935 \end{array}$ | |
| | from which | |
| | A fir, 14 ins. diam., brs. N. 40° W., 246 lks. dist., marked $\frac{1}{4}$ S 6 B T | |
| | A fir, 14 ins. diam., brs. S. 58° W., 99 lks. dist., marked $\frac{1}{4}$ S. 7 B T | |
| | Continue to desc. 10 ft. over SW. slope. | |
| 41.00 | Creek, 2 lks. wide, course SE.; asc. 498 ft. over broken SE. slope. | |
| 57.87 | Yellow Jacket Road, brs NW. and SE. | |
| 72.40 | Flat topped ridge, brs. N. & S.; desc. 113 ft. over W. slope, | |
| 80.00 | Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for cor. of lots 1, 2, 10, and 11, with brass cap marked | |
| | $\begin{array}{r} S\ 6 \\ 10\ \ 11 \\ \hline E\ \ \ \ 1 \\ S\ 7 \\ \hline 1935 \end{array}$ | |
| | from which | |
| | A fir, 12 ins. diam., brs. N. 50° E., 26 lks. dist., marked L 11 S 6 B T. | |
| | A fir, 14 ins. diam., brs. S. 7° E., 76 lks. dist., marked L 1 S 7 B T. | |
| | Continue to desc. 255 ft. over SW. slope. | |
| 87.00 | Intersect E. bdy. of T 5 N., R. 38 E. | |
| | Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, for closing cor. of secs. 6 & 7, with brass cap marked | |
| | $\begin{array}{r l} T5N & T5N \\ S\ 1 & S\ 6 \\ R38E & S\ 7\ CC \\ & R39E \end{array}$ | |
| | 1935 | |
| | from which | |
| | A fir, 40 ins. diam., brs. N. 55° E., 81 lks. dist., marked T 5 N R 39 E S 6 C C B T | |
| | A fir, 40 ins. diam., brs. S. 74° E., 61 lks. dist., marked T 5 N R 39 E S 7 C C B T. | |
| | From this point the cor. of secs. 1 and 12 only, brs. S. 0° 29' E., 9.50 chs. dist., heretofore described. | |
| | Land; mountainous. Soil; sandy loam, rocky, 3rd rate. Timber, fir, pine, spruce and tamarack Undergrowth, alder, vinemaple, salal, elder, willow, rose, huckleberry, laurel, Oregon grape and buck brush. | |