

S. Bdy. of T. 5 S., R. 30 E. W.M.

Chains		Feet
	<p>Soil; 2nd and 3rd rate, mostly very heavy timber. Scattering in places. Tamarack, Fir and Pine, dense young Pine, Tamarack and Fir, underbrush on E. $\frac{1}{2}$ mile.</p> <p style="text-align: right;">Sept. 6, 1880</p>	
	<p>E. on a true line along the S. Bdy. of Sec. 36.</p> <p style="text-align: right;">Var. 14° 00' E.</p> <p>Along N. face of bluff.</p>	
40.00	<p>Set Tamarack post on N.E. face of bluff for $\frac{1}{4}$ Sec. Cor.</p> <p style="padding-left: 40px;">A Pine 8 ins. diam. brs. N. 24° W. 19 lks. dist.</p> <p style="padding-left: 40px;">A Fir 6 ins. diam. brs. S. 52° W. 11 lks. dist.</p>	
68.00	<p>Creek, 30 lks. wide, course S.E.</p>	
80.00	<p>Set basalt stone 17 x 12 x 6 on S. face of bluff for Cor. to T. 5 S., Rs. 30 and 31 E.</p> <p style="padding-left: 40px;">A Pine 8 ins. diam. brs. N. 48° W. 107 lks. dist.</p> <p style="padding-left: 40px;">A Pine 22 ins. diam. brs. N. 71° E. 128 lks. dist.</p>	
	<p>Land; surface very broken,</p> <p>Soil; 3rd and part worthless. Mostly heavy timber, Tamarack, Fir and Pine. Some open glades. Much dense young growth of timber underbrush.</p>	
	<p>Exterior Bdy. of T. 5 S., R. 31 E., W.M. As surveyed by George S. Pershin, U.S. Deputy Surveyor, Under Contract No. 373, Dated Sept. 17, 1880</p>	
	<p>I begin at the stone the Cor. to Tps. 5 S., Rs. 30 & 31 E. on 1st Standard parallel S.</p> <p style="padding-left: 40px;">A Pine 8 ins. diam. brs. N. 48° W. 107 lks. dist.</p> <p style="padding-left: 40px;">A Pine 22 ins. diam. brs. N. 71° E. 128 lks. dist.</p> <p>Cor in good repair. A stone 17 x 12 x 6 in mound of stone and with Burts Improved Solar Compass (Young of Philadelphia Maker) I run,</p> <p>N. on the W. Bdy. of Sec. 31,</p> <p style="text-align: right;">Var. 21° 00' E.</p> <p>Steep ascent.</p>	
23.00	<p>On creek bluff, course S.E. and N.W.</p>	
38.00	<p>Enter timber, course S.E. and N.W.</p>	