

S. Bdy., T.5 S., R.31 E., W. M.

Chains	
	<p>A fir, 14 ins. diam., brs. N.64°E., 50 lks. dist. Camas Creek, 75 lks. wide, course S.E. Land; surface very steep & precipitous. Soil; mostly 3rd rate, some worthless, some 2nd rate on W. $\frac{1}{2}$ mile. A few scattering pine trees, no underbrush. Good bunch grass.</p>
	<p>E. on true line along the S. Bdy. of Sec. 33. Var. 20°30'E. Steep ascent.</p>
40.00	<p>Set basalt stone, 14 x 10 x 8, on top of bluff, for $\frac{1}{2}$ Sec. Cor. A pine, 36 ins. diam., brs. N. 18°W., 64 lks. dist. A pine, 36 ins. diam., brs. S. 13°W., 119 lks. dist.</p>
80.00	<p>Set basalt stone, 18 x 7 x 6, on level, for Cor. to Secs. 33 & 34. A pine, 8 ins. diam., brs. N. 58°W., 64 lks. dist. A pine, 8 ins. diam., brs. N. 54°E., 39 lks. dist. Land; surface W. $\frac{1}{2}$ mile, very steep broken & rocky. E. $\frac{1}{2}$ mile nearly level. Soil; 3rd & 2nd rate. Heavy timber on W. $\frac{1}{2}$ mile, E. $\frac{1}{2}$ mile scattering. Pine, fir & tamarack. Some underbrush on W. $\frac{1}{2}$ mile, E. $\frac{1}{2}$ mile open and good bunch grass.</p>
	<p>E. on true line along S. Bdy. of Sec. 34. Var. 20°15'E.</p>
40.00	<p>Set basalt stone, 18 x 10 x 4, on E. face of small bluff, for $\frac{1}{2}$ Sec. Cor. A pine, 24 ins. diam., brs. N. 3°W., 133 lks. dist. A pine, 20 ins. diam., brs. S. 7°E., 41 lks. dist.</p>
40.50	<p>A ravine opens E.</p>
80.00	<p>Set basalt stone, 20 x 12 x 8 & post, in mound of stone, on W. slope, for Cor. to Secs. 34 & 35. Stone mound, 4 ft. diam. & 2 ft. high. No trees.</p>