

South Bdy., T.5 S.,R.31 E.,W. M.

Chains

Land; surface undulating and sloping W.  
 Soil; 2nd rate. Good grass.  
 Scattering groves of pine timber. No brush.  
 Sept. 7, 1880.

E. on true line along S. Bdy. of Sec. 35.  
 Var.19°45'E.

40.00 Set basalt stone, 20 x 14 x 12, on level, for  $\frac{1}{4}$  Sec.Cor.,  
 in mound of stone. No trees.

40.50 Wagon road, course N. & S.

80.00 Set basalt stone, 18 x 14 x 5 & post, in mound of stone,  
 on slight N. slope, for Cor. to Secs. 35 & 36. No trees.

Land; surface undulating.  
 Soil; 2nd rate, some 3rd rate and stony.  
 Occasional groves of pine timber. Good grass.  
 Some farming land, but mostly grazing.

E. along S. Bdy. of Sec. 36, on true line.  
 Var.19°15'E.

40.00 Set basalt stone, 20 x 8 x 7, on slight N.W. slope,for  $\frac{1}{4}$   
 Sec. Cor. No trees.

80.00 Set basalt stone, 22x11 x 8 & post, in mound of stone, on  
 slight N.W. slope, for Cor. to Tps. 5 S.,Rs.31 & 32 E.

A pine, 42 ins. diam.,brs. N.52°E., 159 lks. dist.

No other tress.

Land; surface undulating.  
 Soil; 2nd & 3rd rate.  
 Some sacttering pine timber; good bunch grass.  
 Some good farming land, but mostly only good for grazing.

Subdivisional Lines, T. 5 S.,R.31 E.,W. M.  
 As surveyed by Geo. S. Pershin,  
 Under Contract No. 373,  
 Dated Sept. 17, 1880.

To compare the chaining of my present assistants, with my  
 former ones, I begin at the S.E. Cor. of Sec. 36, and  
 withthe same compass, I run