

Subdivisional Lines, T.5 S., R.31 E., W. M.

Chains	E. on random line bet. Secs. 1 & 12. Var.19°30'E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.90	Intersected E. Bdy., 18 lks. N. of Cor. to Secs. 1 & 12, from from which Cor. I run N.89°52'W. on true line bet. Secs. 1 & 12. Var.19°45'E.
39.95	Set basalt stone, 16 x 10 x 4 on level, in open glade, for $\frac{1}{4}$ Sec. Cor. A pine, 10 ins. diam., brs. S.34°E., 152 lks. dist. No other trees.
79.90	The Cor. to Secs. 1, 2, 11 & 12. Land; surface undulating. Soil; 1st & 2nd rate. Heavy pine, fir & tamarack timber, with open glades. Will be good farming land when cleared.
	N. on random line bet. Secs. 1 & 2. Var.19°30'E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.87	Intersected N. Bdy., 28 lks. W. of Cor. to Secs. 1 & 2, from which Cor., I run S.00°12'W. on true line bet. Secs. 1 & 2. Var.19°30'E.
6.50	Owens Creek, 12 lks. wide, course W.
8.00	Enter timber, course E. & W.
28.00	Wagon road, course S.W. & N.E.
39.87	Set pine post, on level, for $\frac{1}{4}$ Sec. Cor. A pine, 20 ins. diam., brs. S., 7 lks. dist. A pine, 22 ins. diam., brs. N.82°W., 40 lks. dist.
79.87	The Cor. to Secs. 1, 2, 11 & 12. Land; surface undulating. Soil; 2nd & 1st rate. Heavy timber, with open glades, pine, tamarack & fir. Good farming land.