

Subdivisional Lines, T.5 S., R.31 E., W. M.

Chains	
	Land; surface undulating. Soil; 1st & 2nd rate. Good grass. Well adapted to farming.
	E. on random line bet. Secs. 2 & 11. Var. 19°45'E.
40.00	Set post, for temp. $\frac{1}{4}$ Sec. Cor.
79.66	Intersected N. & S. line, 18 lks. S. of Cor. to Secs. 1, 2, 11 & 12, from which Cor., I run S. 89°52'W., on true line bet. Secs. 2 & 11. Var. 19°30'E.
12.00	Leave timber, course N. & S.
19.00	Wagon road, course N.E. & S.W.
39.83	Set basalt stone, 16 x 10 x 8, on N.W. slope, in mound of stone, for $\frac{1}{4}$ Sec. Cor.
79.66	The Cor. to Secs. 2, 3, 10 & 11. Land; surface undulating. Soil; 1st & 2nd rate, small part 3rd rate. E. 12 chs. pine timber. Excellent grass. Well adapted to farming.
	N. on random line bet. Secs. 2 & 3. Var. 19°45'E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.88	Intersected N. Bdy., 8 lks. E. of Cor. to Secs. 2 & 3, from which Cor., I run S. 00°04'E. on true line bet. Secs. 2 & 3. Var. 19°30'E.
34.50	Snipe Creek, 16 lks. wide, course S.W.
39.88	Set basalt stone, 14 x 6 x 4 & post, in mound of stone, on level, for $\frac{1}{4}$ Sec. Cor.
56.00	Ellis' house brs. E., 250 lks.
79.88	The Cor. to Secs. 2, 3, 10 & 11. Land; surface nearly level. Soil; 1st rate. Good grass. Good natural meadow; excellent farming land. Oct. 6, 1880.