

Exterior Lines of T. 5 S., R. 32 E., W.M.

Chains		Feet
	Land; surface undulating Soil; 2nd and 3rd rate. Good grass. Some scattering pine timber. Some good farming land.	
	N. on the E. Bdy. of Sec. 1 Var. 20° 45' E.	
40.00	Set basalt stone, 16 x 12 x 4, on level in mound of stone for $\frac{1}{4}$ Sec. Cor.	
54.50	A brook, 30 lks. wide, course N.W. and deep canyon	
80.00	Set Pine post, 5 ins. sq. and 5 ft. long in mound of stone on level for Cor. to Tps. 4 and 5 S., Rs. 32 and 33 E. No trees near. Land; surface slightly undulating, except brook canyon Soil; 3rd and 2nd rate. heavy Pine, Tamarack and Fir timber in canyon. Good grass on prairie. May 30, 1881. Note:- Took observation on Polaris, upon trial, my compass indicates an error 8' W. of meridian.	
	Subdivisional Lines of T. 5 S., R. 32 E., W.M. As surveyed by, George S. Pershin, U.S. Deputy Surveyor, Under Contract No. 390, Dated May 12, 1881.	
	N. bet. Sec. 35 & 36 Var. 18° 45' E.	
	A Tamarack, 24 ins. diam. brs. N. 46° E., 30 lks, dist. A " 14 " " " N. 40° W. 79 " "	
40.00	Set basalt stone, 17 x 12 x 5 on slight N. slope for $\frac{1}{4}$ Sec. Cor. A Pine, 15 ins. diam. brs. N. 85° E., 28 lks. dist. A Pine, 20 ins. diam. brs. S. 84° W., 81 lks. dist.	
43.00	Spring branch, course N.W.	
48.00	Leave timber, course S.E. and N.W.	
80.00	Set basalt stone, 24 x 12 x 5, and post in mound of stone on slight W. slope for Cor. to Sec. 25, 26, 35 and 36. Land; surface undulating,	