

Exterior Lines, T.5 S., R.33 E., W. M.

Chains

43.00 A pine, 10 ins. diam., brs. N.38 ° W., 12 lks. dist.,
Camas creek, 20 lks. wide, course W.

44.50 Leave creek bottom, begin ascent, timber becomes scatter-
ing.

80.00 Set pine post, 5 ins. sq., 5 ft. long, on level, in large
open glade, for Cor. to Tps. 4 & 5 S., Rs., 33 & 34 E.,
marked

T.4 S., R.34 E., S.31 on N.E. side
T.5 S., R.34 E., S.6 on S.E. "
T.5 S., R.33 E., S.1 on S.W. "
T.4 S., R.33 E., S.36 on N.W. "

Also marked with 6 notches on N., E., S. & W. edges.
Raised mound of stone, 2½ ft. high and 5½ ft. base
around post, in lieu of pits.

Land; surface rolling and undulating.
Soil; 3rd & 2nd rate.
Scattering pine timber.

Sept. 6, 1881.

General Description.

The S.E. part is mountainous, the N. & W. part, rolling &
undulating, with considerable part, nearly level.

Soil, about equally 3rd & 2nd rate, with some 1st rate,
about 2/5 is heavily timbered, about 1/5 is open prairie
or scattering timber, about 1/5 is agricultural land
and is located mostly on N. & W. sides.

This Tp. should be subdivided at an early day.

Resurvey of W. Bdy. of T.5 S., R.33½ E., W. M.
As surveyed by Rufus S. Moore, U.S. Deputy Surveyor,
Under Contract No. 451
Dated June 12, 1882.

Resurvey of W. Bdy. of Tp., as the Cors. on W. Bdy. of
this Tp. are 17.28 chs. N. of point for Cors. necessary
for the subdivisions of T.5 S., R.33½ E., I am compelled
to resurvey it.
Begin at Closing Cor. to T.5 S., R.33½ E. and run,