

Resurvey W. Bdy., T.5 S., R.33 $\frac{1}{2}$ E., W. M.

Chains	
	<p>marked T.5 S., R.34 E., S.7, B.T.</p> <p>A pine, 16 ins. diam., brs. S.38°E., 55 lks. dist., marked T.5 S., R.34 E., S.18, B.T.</p> <p>A pine, 18 ins. diam., brs. S.40°W., 93 lks. dist., marked T.5 S., R.33 E., S.13, B.T.</p> <p>A pine, 24 ins. diam., brs. N.66°W., 46 lks. dist., marked T.5 S., R.33 E., S.12, B.T.</p> <p>Destroyed marks referring to Secs. 7 & 18.</p>
54.90	The $\frac{1}{4}$ Sec. Cor.
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 3 & 10, marked</p> <p>T.5 S., R.33$\frac{1}{2}$ E. on E. S. 3 on N. and S.10 on S. faces, with 5 notches on S. and 1 notch on N. faces, and mound of stone around post, from which, A pine, 5 ins. diam., brs. N.43°E., 69 lks. dist., marked T.5 S., R.33$\frac{1}{2}$ E., S.3, B.T.</p> <p>Land; mountainous. Soil; 2nd & 3rd rate. Heavily timbered with pine, fir & tamarack.</p> <hr/> <p>N. on W. Bdy. of Sec. 3. Var. 19°30'E.</p> <p>Gradual descent,</p>
14.65	<p>The Cor. to Secs. 1 & 12, which is a basalt stone, 16 x 10 x 5, marked with 5 notches on S. and 1 notch on N. edges from which,</p> <p>A pine, 6 ins. diam., brs. N.9°E., 90 lks. dist., marked T.5 S., R.34 E., S.6, B.T.</p> <p>A pine, 8 ins. diam., brs. S.68°E., 88 lks. dist., marked T.5 S., R.34 E., S.7, B.T.</p> <p>A pine, 8 ins. diam., brs. S.75°W., 138 lks. dist., marked T.5 S., R.33 E., S.12, B.T.</p> <p>A pine, 8 ins. diam., brs. N.48°W., 139 lks. dist.,</p>