

Subdivisional Lines, T.5 S., R.33 E., W. M.

Chains	
18.00	Top of irregular ridge, course E. & W., 200 ft. high.
27.50	A ravine, course S.W., 150 ft. descent.
40.00	Top of ridge, course E. & W. Set Set pine post, marked $\frac{1}{4}$ S. on W. side, on level, for $\frac{1}{4}$ Sec. Cor., from which A fir, 24 ins. diam., brs. S.38°E., marked $\frac{1}{4}$ S., B.T. 16 lks. dist. A pine, 22 ins. diam., brs. N.72°W., 59 lks. dist., marked $\frac{1}{4}$ S., B.T.
80.00	Set basalt stone, 14 x 10 x 8 ins., 9 ins. in ground, for Cor. to Secs. 25, 26, 35 & 36, marked with 1 notch on S. and 1 notch on E. edges, S. slope, from which A pine, 10 ins. diam., brs. N.84°E., 63 lks. dist., marked T.5 S., R.33 E., S.25, B.T. A fir, 8 ins. diam., brs. S.48°E., 68 lks. dist., marked T.5 S., R.33 E., S.36, B.T. A pine, 14 ins. diam., brs. S.82°W., 34 lks. dist., marked T.5 S., R.33 E., S.35, B.T. A fir, 16 ins. diam., brs. N.62°W., 16 lks. dist., marked T.5 S., R.33 E., S.26, B.T. Land; surface mountainous. Soil; 3rd rate. Some green timber, but mostly burnt & dead and much of it down, pine, fir & tamarack. Some underbrush of same.
	E. on random line bet. Secs. 25 & 36. Var. 20°15'E.
19.50	Hidaway Creek, 60 lks. wide, course N., 300 ft. below Sec. Cor.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
70.00	Top of irregular hill, 400 ft. above creek.
79.84	Intersected E. Bdy., 72 lks. N. of Cor. to Secs. 25 & 36, which is a basalt stone on S.E. slope. A fir, 24 ins. diam., brs. N.66°E., 55 lks. dist., marked T.5 S., R.34 E., S.30, B.T. A pine, 12 ins. diam., brs. S.68°E. 98 lks. dist.,