

Subdivisional Lines, T.5 S., R.33 E., W. M.

| Chains | |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | <p>A pine, 10 ins. diam., brs. N.62°E., 33 lks. dist., marked T.5 S., R.33 E., S.24, B.T.</p> <p>A fir, 12 ins. diam., brs. S.56°E., 65 lks. dist., marked T.5 S., R.33 E., S.25, B.T.</p> <p>A spruce, 8 ins. diam., brs. N.70°W., 34 lks. dist., marked T.5 S., R.33 E., S.23, B.T.</p> <p>No tree S.W.</p> <p>Land; surface, very broken and mountainous.</p> <p>Soil; 3rd & 2nd rate.</p> <p>Heavily timbered with pine, tamarack & fir timber, with underbrush the same.</p> |
| | <p>E. on random line bet. Secs. 24 & 25.</p> <p style="text-align: right;">Var. 20°30'E.</p> <p>Irregular ascent S.W. face of bluff.</p> |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. |
| 79.36 | <p>Intersected E. Bdy., 68 lks. N. of Cor. to Secs. 23 & 24, which is a stone, about 8 ins. above ground.</p> <p>A pine, 18 ins. diam., brs. N.46°E., 245 lks. dist., marked T.5 S., R.33 E., S.19, B.T.</p> <p>A pine, 12 ins. diam., brs. S.18°W., 158 lks. dist., marked T.5 S., R.33 E., S.25, B.T.</p> <p>No other trees marked.</p> <p>From which Cor., I run</p> <p>N.89°31'W. on true line bet. Secs. 24 & 25.</p> <p style="text-align: right;">Var. 19°20'E.</p> |
| 39.68 | <p>Set basalt stone, 18 x 10 x 6 ins., 12 ins. in ground, on S.W. slope, marked $\frac{1}{4}$ on N. face, for $\frac{1}{4}$ Sec. Cor.</p> <p>A pine, 30 ins. diam., brs. N.28°E., 60 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> <p>A pine, 14 ins. diam., brs. S.48°W., 36 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> |
| 79.36 | <p>The Cor. to Secs. 23, 24, 25 & 26.</p> <p>Land; surface mountainous.</p> <p>Soil; 3rd rate.</p> <p style="text-align: right;">May 29, 1882.</p> <p>Heavily timbered with pine timber, with open glades.</p> |