

## Subdivisional Lines, T.5 S., R.33 E., W. M.

| Chains |   |
|--------|---|
| 79.64  | <p>Intersected N. &amp; S. line, 40 lks. N. of Cor. to Secs. 20, 21, 28 &amp; 29, from which Cor., I run<br/>N.89°43'W. on true line bet. Secs. 20 &amp; 29.<br/>Var.20°30'E.</p>   |
| 39.82  | <p>Set basalt stone, 14 x 8 x 8 ins., 9 ins. in ground, on slight N. slope, for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> on N. side.<br/>A fir, 16 ins. diam., brs. N.58°W., 13 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.<br/>A tamarack, 14 ins. diam., brs. S.26°E., 62 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p>  |
| 79.64  | <p>The Cor. to Secs. 19, 20, 29 &amp; 30.<br/>Land; surface undulating.<br/>Soil; 3rd &amp; 2nd rate.<br/>Mostly open prairie, some scattering groves of pine timber.<br/>Good grass.</p>   |
|        | <p>W. on random line bet. Secs. 19 &amp; 30.<br/>Var.20°00'E.<br/>Slightly descending.</p>  |
| 40.00  | <p>Set temp. <math>\frac{1}{4}</math> Sec. Cor.</p>   |
| 79.20  | <p>Intersected W. Bdy., 72 lks. N. of Cor. to Secs. 19 &amp; 30, descent about 100 ft., which Cor. is a stone, set in a mound of stone,<br/>A pine, 28 ins. diam., brs. S.4°E., 146 lks. dist., marked T.5 S., R.33 E., S.30, B.T.<br/>A pine, 26 ins. diam., brs. S.12°W., 177 lks. dist., marked T.5 S., R.32 E., S.25, B.T.<br/>From which Cor., I run<br/>N.89°29'E. on true line bet. Secs. 19 &amp; 30.<br/>Var.29° 15'E.</p> |
| 39.20  | <p>Set basalt stone, 18 x 12 x 10 ins., 12 ins. in ground, on slight N.W. slope, for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> on N. face<br/>Raised mound of stone alongside, in lieu of pits.</p>   |
| 79.20  | <p>The Cor. to Secs. 19, 20, 29 &amp; 30.<br/>Land; surface undulating. Soil; 2nd &amp; 1st rate. Good grass.<br/>No timber on line.</p>  |