

W. Bdy., T.5 S., R.34 E., W. M.

Chains	Heavily timbered with pine, fir & tamarack, 80 chs.
N. bet. Secs. 25 & 30.	Var. 20°E.
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which</p> <p>A pine, 6 ins. diam., brs. S. 85°W., 22 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> <p>A pine, 4 ins. diam., brs. E., 2 lks. dist., marked $\frac{1}{4}$ S., B.T.</p>
72.50	<p>Descend. Brook, 2 lks. wide, runs E., about 200 ft. below $\frac{1}{4}$ Sec. Cor.</p>
80.00	<p>Set pine post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 19, 24, 25 & 30, marked</p> <p>T.5 S., S.19 on N.E.</p> <p>R.34 E., S.30 on S.E.</p> <p>R.33$\frac{1}{2}$ E., S.25 on S.W. and S.24 on N.W. faces, with</p> <p>4 notches on N. and</p> <p>2 notches on S. edges, from which</p> <p>A pine, 4 ins. diam, brs. S. 80°E., 7 lks. dist., marked T.5 S., R.34 E., S.30, B.T.</p> <p>A tamarack, 13 ins. diam., brs. N. 62°E., 30 lks. dist., marked T.5 S., R.34 E., S.19, B.T.</p> <p>A pine, 4 ins. diam., brs. S. 36°W., 18 lks. dist., marked T.5 S., R.33$\frac{1}{2}$ E., S.25, B.T.</p> <p>A pine, 4 ins. diam., brs. N. 45°W., 29 lks. dist., marked T.5 S., R.33$\frac{1}{2}$ E., S.24, B.T.</p>
	Land; hilly.
	Soil; 3rd rate.
	Heavily timbered with pine, fir & tamarack, 80 chs.
	Dense undergrowth of small pine, fir & tamarack, 80 chs.
N. bet. Secs. 19 & 24.	Var. 20°E.
36.00	Brook, 5 lks. wide, runs W., 150 ft. below Cor.
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$