

Subdivisional Lines, T.5 S., R.33½ E., W. M.

Chains	<p>¼ Sec. Cor., marked ¼ on W. face, from which</p> <p>A pine, 10 ins. diam., brs. N.70°W., 102 lks. dist., marked ¼ S., B.T.</p> <p>A fir, 16 ins. diam., brs. S.60°E., 84 lks. dist., marked ¼ S., B.T.</p>
80.00	<p>Thence along hillside facing W.</p> <p>Set basalt stone, 13 x 8 x 7 ins., 10 ins. in ground, for Cor. to Secs. 13, 14, 23 & 24, marked with 3 notches on S. and 1 notch on E. edges, from which</p> <p>A juniper, 20 ins. diam., brs. S.45°W., 21 lks. dist., marked T.5 S., R.33½ E., S.23, B.T.</p> <p>A juniper, 20 ins. diam., brs. N.49°W., 58 lks. dist., marked T.5 S., R.33½ E., S.14, B.T.</p> <p>A fir, 20 ins. diam., brs. N.74°E., 85 lks. dist., marked T.5 S., R.33½ E., S.13, B.T.</p> <p>A mahogany, 10 ins. diam., brs. S.47°E., 22 lks. dist., marked T.5 S., R.33½ E., S.24, B.T.</p>
	<p>Land; rolling.</p> <p>Soil; 3rd rate.</p> <p>Heavily timbered with fir, & pine on S. 40 chs.</p> <p>Dense undergrowth of fir & pine on N. 40 chs.</p> <p>Scattering juniper and mahogany; good bunch grass.</p>
	<p>E. on random line bet. Secs. 13 & 24.</p> <p style="text-align: right;">Var. 20°E.</p>
	<p>Over rolling ground.</p> <p>Through timber.</p>
37.00	A creek, 6 lks. wide, course N.W.
40.00	Set temp. ¼ Sec. Cor.
79.92	<p>Intersect E. line of Tp. at Cor. to Secs. 13, 18, 19 & 24, which is a post, 4 ins. sq., firmly set in ground, marked</p> <p style="text-align: center;">T.5 S., S.18 on N.E.</p> <p style="text-align: center;">R.34 E., S.19 on S.E.</p> <p style="text-align: center;">R.33½ E., S.24 on S.W. and</p> <p style="text-align: center;">S.13 on N.W. faces, with</p> <p style="text-align: center;">3 notches on N. & S. edges, from which</p>