

Subdivisional Lines, T.5 S., R.35 $\frac{1}{2}$ E., W: M.

Chains

- 80.00 The Cor. to Secs. 11, 12, 13 & 14.
 Land; rolling.
 Soil; 2nd rate.
 Heavily timbered with pine, fir & tamarack.
 Dense undergrowth of pine, fir & tamarack.
-
- N. bet. Secs. 11 & 12.
 Var. 20°10'E.
 Over rolling ground.
- 34.00 Descend, course E. & W. to Camas valley.
- 40.00 Set basalt stone, 18 x 18 x 18 ins., 12 ins. in ground, for
 $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which
 A pine, 8 ins. diam., brs. S.22°W., 41 lks. dist.,
 marked $\frac{1}{4}$ S., B.T.
 A tamarack, 10 ins. diam., brs. N.35°E., 15 lks. dist.,
 marked $\frac{1}{4}$ S., B.T.
- 66.00 Foot of descent.
 A ravine, course W.
- 72.00 A pine, 40 ins. diam. & leave timber, N.E. & W.
- 80.00 Set basalt stone, 16 x 10 x 9 ins., 12 ins. in ground, for
 Cor. to Secs. 1, 2, 11 & 12, marked with 5 notches on S.
 and 1 notch on E. edges, from which
 A pine, 40 ins. diam., brs. S.54°E., 240 lks. dist.,
 marked T.5 S., R.35 $\frac{1}{2}$ E., S.12, B.T.
 No other trees within limits.
 Raised mound of stone alongside.
 Land; rolling.
 Soil; 2nd rate.
 Heavily timbered with pine, fir & tamarack & juniper.
 Dense undergrowth of pine, fir, tamarack & juniper, S.72
 chains.
-
- E. on random line bet. Secs. 1 & 12.
 Var. 19°30'E.
 Over rolling prairie.
- 36.00 Enter dense forest, course N. & S.